



# Platform Resurfacing Project Case Study



H&A Rail Ltd was successful in winning a bid to resurface 6 Platforms on 3 major London Northwest stations, within a 6 day blockade in Dec 2022.

Working in collaboration with our key client and valued supply chain we completed all works with no accidents or incidents.

A major job successfully completed, within a set time constraint, and a happy client at the end of the project.





- Removed over 500t of old concrete pavers and soil
- Protected all platform assets while works took place
  - Installed 100t of new MOT Type 1 Subbase
  - Installed 300m of platform edgings
  - Installed 1000m of Densoband
  - Lifted and re-bed 80m of platform tactile
  - Installed 200t of new tarmac
- Lifted and installed new platform edge copers that were damaged
  - Installed safety corduroy tactile

E: [info@harail.co.uk](mailto:info@harail.co.uk) | T: 0208 611 2790



The platform for all your inbound railway projects